BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer,
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/09/2022-23 Dated:10-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 13

Name of Work:-Maintenance of Ganesh immersion tank at Attur Kalyani in Attur ward no:04 Yelahanka Satellite Town Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri PRUTHVIRAJ N	
				Rate	Rate in Words
1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates /Sand/Kankar/Moorum.(Tipper 5.5 m3) Removal of Silt in Kalyani	Cum	416.00	177.18	One Hundred SeventySeven Paise Eighteen Only
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/ Moorum.(Tipper 5.5 m3) Depth exceeding 1.5m, but not exceeding 3 m	Cum	416.00	171.23	One Hundred SeventyOne Paise TwentyThree Only
3	Supply of water Through water Tank for filling Tank	Each	234.00	311.76	Three Hundred Eleven Paise SeventySix Only
4	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to sliping	Cum	6.00	866.00	Eight Hundred SixtySix Only
5	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	78.00	36.37	ThirtySix Paise ThirtySeven Only
6	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	234.00	377.75	Three Hundred SeventySeven Paise SeventyFive Only

Scanned with CamScanner

	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	Mtrs	1236.00	56.29	FiftySix Paise TwentyNine Only
8	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 20ft x 30ft = 600 sqft)	Sft	9100.00	6.93	Six Paise NinetyThree Only
9	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 13x 18ft = 150 Rft)	Rft	2340.00	14.72	Fourteen Paise SeventyTwo Only
10	Hire Charge for Armless Plastic Chairs	Nos	234.00	3.46	Three Paise FourtySix Only
11	Hire Charge for Wooden Table of Size 6ft x 2ft	Nos	65.00	34.64	ThirtyFour Paise SixtyFour Only
12	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire	Mtrs	1170.00	7.79	Seven Paise SeventyNine Only
13	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges	Hr	66.00	462.44	Four Hundred SixtyTwo Paise FourtyFour Only
14	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time	Nos	78.00	246.81	Two Hundred FourtySix Paise EightyOne Only
15	Hire charges compoment name 1087 Crane charges	Day	13.00	2935.74	Two Thousand Nine Hundred ThirtyFive Paise SeventyFour Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Scanned with CamScanner